



# Quality Control Inspection SOP

Final sign-off before vehicle delivery

SOP · Version 1.0

Organization: \_\_\_\_\_

Document ID: qc-inspection-sop

Effective Date: \_\_\_\_\_

Approved By: \_\_\_\_\_

# Quality Control Inspection SOP

---

**Final sign-off before vehicle delivery**

---

## Purpose

---

Ensure every completed job meets shop standards before customer notification.

## Scope

---

All installation and detailing services. Lead installer or designated QC inspector signs off.

# Procedure

---

## Step 1 — Environment

1. Move vehicle to QC zone with adequate cross-lighting
2. Vehicle must be clean enough to evaluate finish (no wash residue on evaluation areas)

## Step 2 — Edge audit

1. Inspect every edge, seam, and termination point
2. Verify post-heat completed per manual standards
3. No lifting, contamination, or incomplete tuck

## Step 3 — Optical inspection

1. View every panel at multiple angles
2. Check for bubbles, fingers, scratches, haze, or debris
3. Document with photos — minimum 4 exterior angles + 2 detail shots

## Step 4 — Sign-off

1. Complete Post-Install QC Checklist
2. Lead installer signs work order
3. Notify CS for delivery scheduling

# Fail criteria — do not deliver

---

Any visible defect, edge lift, contamination, or scope deviation requires rework before delivery. No exceptions for "customer won't notice."

## Related documents

---

| Document                  | ID                        |
|---------------------------|---------------------------|
| Post-Install QC Checklist | post-install-qc-checklist |
| Delivery Walkthrough SOP  | delivery-walkthrough-sop  |

---

Confidential — Skill Forge training operations.