



SOP-202 — Decontamination

Section 3: Installation Operations

SOP · Version 1.0

Organization: _____

Document ID: sop-202-decontamination

Effective Date: _____

Approved By: _____

SOP-202 — Decontamination

Forge Standard Operating Procedures v1.0

Section 3: Installation Operations

Purpose

Remove bonded contaminants so film adheres to a chemically clean surface.

Scope

All PPF, wrap, and TPU installs. Select steps per service manual.

Procedure

Chemical decon

1. Iron remover on paint — dwell per product label, rinse thoroughly.
2. Tar and adhesive remover on affected areas only.
3. Panel wipe with IPA 70% (or manufacturer-specified prep solution) immediately before install.

Mechanical decon

1. Clay bar or clay mitt with lubricant on paint surfaces receiving film.
2. Glass: steel wool 0000 + glass cleaner on tint jobs only where manual specifies.
3. Final IPA wipe — one direction, fresh towel per section.

Contamination control

1. No silicone-based dressings in install bay before or during job.
2. Installers wash hands; nitrile gloves for final prep.
3. Vehicle cannot leave decon bay through customer waiting area.

Checkpoint: Water break test passes on paint (sheet flow, no beading spots) before PPF/wrap.

Quality standards

- ☐ Zero adhesion failures traced to prep on QC review
- ☐ IPA wipe within 30 minutes of first panel install

Related documents

Document	ID
PPF Surface Prep (workflow)	sop-400-complete-ppf-installation-workflow
Pre-Install QC Checklist	pre-install-qc-checklist

Revision history

Version	Date	Author	Changes
1.0	2026-07-23	Forge Operations	Initial release

Confidential — Skill Forge training operations.