



SOP-203 — Installation Bay Setup

Section 3: Installation Operations

SOP · Version 1.0

Organization: _____

Document ID: sop-203-installation-bay-setup

Effective Date: _____

Approved By: _____

SOP-203 — Installation Bay Setup

Forge Standard Operating Procedures v1.0

Section 3: Installation Operations

Purpose

Configure a clean, organized bay for maximum quality and efficiency.

Scope

Before every job. Lead installer or assigned tech.

Procedure

Bay environment

1. Complete Daily Bay Reset Checklist.
2. Verify lighting — no burned-out LEDs in primary work zone.
3. Dust sweep; damp-mop if floor visible dirty.
4. Close bay doors during active install to limit dust ingress.

Equipment layout

1. Heat gun on stand; extension cords routed overhead, not across walk paths.
2. Solution bottles labeled and filled; blades in dispenser.
3. Plotter warmed up if computer-cut job.
4. Trash and film liner bins within arm's reach.

Job staging

1. Pull work order; confirm film lot numbers match job card.
2. Stage patterns or roll film at bay entry.
3. Post "Bay Occupied" sign if customers have bay sightlines.

Quality standards

- ☐ Bay reset between every job
- ☐ Film lot traceable to work order

Related documents

Document	ID
Daily Bay Reset Checklist	daily-bay-reset-checklist
Tool Preparation	sop-204-tool-preparation
Shop Opening Procedure	sop-003-shop-opening-procedure

Revision history

Version	Date	Author	Changes
1.0	2026-07-23	Forge Operations	Initial release

Confidential — Skill Forge training operations.