



Daily Bay Opening & Closing SOP

Start and end of every production day

SOP · Version 1.0

Organization: _____

Document ID: bay-opening-closing-sop

Effective Date: _____

Approved By: _____

Daily Bay Opening & Closing SOP

Start and end of every production day

Opening procedure

1. Lights on — verify all bay lighting operational
2. Sweep and blow floors; empty trash
3. Wipe work surfaces with approved cleaner
4. Verify slip solution, IPA, and consumables stocked
5. Heat guns, plotters, and tools on shadow board — accounted for
6. Review day's job queue and material pull list
7. Team huddle — 5 minutes: priorities, risks, coverage gaps

Closing procedure

1. All vehicles secured — keys in lockbox, bays labeled
2. Tools cleaned and returned to shadow board
3. Film scraps disposed; material logged in inventory
4. Floors swept; contamination control maintained
5. Equipment off (heat guns, plotters, compressors per shop policy)
6. CRM updated — status on every active job
7. Alarm set; doors locked

Related documents

Document	ID
Daily Bay Reset Checklist	daily-bay-reset-checklist
Contamination Control SOP	contamination-control-sop

Confidential — Skill Forge training operations.