



SKILL FORGE
— WHERE STUDENTS BECOME TEAM

SOP-200 — Vehicle Inspection

Section 3: Installation Operations

SOP · Version 1.0

Organization: _____

Document ID: sop-200-vehicle-inspection

Effective Date: _____

Approved By: _____

SOP-200 — Vehicle Inspection

Forge Standard Operating Procedures v1.0

Section 3: Installation Operations

Purpose

Assess paint, glass, and substrate condition before any installation work begins.

Scope

Lead installer or designated prep tech. After CS check-in, before wash or decon.

Procedure

Lighting & documentation

1. Position vehicle in inspection lighting — minimum 1000 lux on horizontal surfaces.
2. Verify CS inspection form on file; re-walk if gaps exist.
3. Photograph every panel at 3 angles minimum.

Paint & substrate assessment

1. Note swirls, chips, rust, repaints, PDR, and aftermarket parts.
2. Identify high-risk areas: rubber trim, badges, sensors, panoramic roofs.
3. Flag paint correction requirement before film install — stop if customer declined correction on swirled panels.

Production notes

1. Enter findings on work order — installer-facing notes.
2. Complete Pre-Install QC Checklist.
3. Escalate scope changes to manager before proceeding.

Quality standards

- ☐ Pre-install checklist on 100% of jobs
- ☐ No film applied over undisclosed pre-existing damage

Related documents

Document	ID
Pre-Install QC Checklist	pre-install-qc-checklist
Vehicle Check-In	sop-103-vehicle-check-in
PPF Master Install Manual	ppf-master-install

Revision history

Version	Date	Author	Changes
1.0	2026-07-23	Forge Operations	Initial release

Confidential — Skill Forge training operations.