



SOP-204 — Tool Preparation

Section 3: Installation Operations

SOP · Version 1.0

Organization: _____

Document ID: sop-204-tool-preparation

Effective Date: _____

Approved By: _____

SOP-204 — Tool Preparation

Forge Standard Operating Procedures v1.0

Section 3: Installation Operations

Purpose

Ensure every tool is clean, functional, and appropriate before touching customer vehicles.

Scope

All installers before starting any job.

Procedure

Cutting & squeegee tools

1. Fresh blade in knife — change every panel or when dull.
2. Inspect squeegees for nicks; swap if edge damaged.
3. Tack cloth squeegee faces before first panel.

Heat & air

1. Heat gun tip clean; test on scrap film for even heat.
2. Compressor moisture drained; air hose filtered.

Chemicals

1. Verify slip solution mix ratio per film manufacturer.
2. IPA bottle labeled with date mixed; discard after 7 days.
3. No unauthorized adhesives or dressings in bay.

Quality standards

- ☐ Zero scratch incidents from dull blades in QC quarter
- ☐ Tool shadow board 100% accounted for at job end

Related documents

Document	ID
Installation Bay Setup	sop-203-installation-bay-setup
Quality Control Inspection	sop-205-quality-control-inspection

Revision history

Version	Date	Author	Changes
1.0	2026-07-23	Forge Operations	Initial release

Confidential — Skill Forge training operations.