



SOP-205 — Quality Control Inspection

Section 3: Installation Operations

SOP · Version 1.0

Organization: _____

Document ID: sop-205-quality-control-inspection

Effective Date: _____

Approved By: _____

SOP-205 — Quality Control Inspection

Forge Standard Operating Procedures v1.0

Section 3: Installation Operations

Purpose

Verify installation meets shop standards before vehicle moves to final inspection.

Scope

All installation services. Performed by lead installer or QC-designated tech — not the sole installer on complex jobs.

Procedure

Environment

1. Move vehicle to QC zone with adequate cross-lighting.
2. Vehicle clean enough to evaluate finish — no wash residue on evaluation areas.

Edge audit

1. Inspect every edge, seam, and termination point.
2. Verify post-heat completed per Master Installer Manual standards.
3. No lifting, contamination, or incomplete tuck.

Optical inspection

1. View every panel at multiple angles.
2. Check for bubbles, fingers, scratches, haze, or debris.
3. Document with photos — minimum 4 exterior angles + 2 detail shots.

Sign-off

1. Complete Post-Install QC Checklist.
2. Lead installer signs work order.
3. Fail → rework before advancing to SOP-206.

Quality standards

- ☐ Post-install checklist on 100% of jobs
- ☐ Comeback rate under shop target (track monthly)

Safety notes



Do not deliver with any visible defect — see fail criteria in Quality Standards Manual.

Related documents

Document	ID
Post-Install QC Checklist	post-install-qc-checklist
Final Inspection	sop-206-final-inspection
Installation Failure	sop-900-installation-failure

Revision history

Version	Date	Author	Changes
1.0	2026-07-23	Forge Operations	Initial release

Confidential — Skill Forge training operations.