



SOP-206 — Final Inspection

Section 3: Installation Operations

SOP · Version 1.0

Organization: _____

Document ID: sop-206-final-inspection

Effective Date: _____

Approved By: _____

SOP-206 — Final Inspection

Forge Standard Operating Procedures v1.0

Section 3: Installation Operations

Purpose

Manager-level sign-off that the vehicle is customer-ready.

Scope

Every vehicle before customer notification. Shop manager or senior lead.

Procedure

Documentation review

1. Work order complete — hours, materials, photos attached.
2. QC checklist signed; any rework noted and resolved.
3. Warranty registration data ready for SOP-702.

Customer-ready audit

1. Repeat edge and optical check at customer viewing height.
2. Interior free of tools, trash, and glove residue.
3. Exterior free of tape marks, solution residue, and fingerprints on glass.

Release

1. Sign final inspection line on work order.
2. Notify CS to schedule delivery (SOP-107).
3. Update CRM status → ready for pickup.

Quality standards

- ☐ Manager sign-off on 100% of retail deliveries
- ☐ Delivery photos match QC photos — no post-QC damage

Related documents

Document	ID
Quality Control Inspection	sop-205-quality-control-inspection
Vehicle Delivery	sop-107-vehicle-delivery
Vehicle Delivery Checklist	vehicle-delivery-checklist

Revision history

Version	Date	Author	Changes
1.0	2026-07-23	Forge Operations	Initial release

Confidential — Skill Forge training operations.